



AFTER MANHOLE IS ADJUSTED, AND ASPHALT CONCRETE HAS BEEN BROUGHT TO GRADE, CONTRACTOR SHALL PERFORM A "HEAT-WELD" IN ACCORDANCE WITH COLS SUPPLEMENTAL SPECIFICATION 1541 TO ENSURE A UNIFORM AND FLUSH TRANSITION.



NOTE: IF LID DOES NOT FIT FLUSH (1/8" +/- TOLERANCE), CONTRACTOR SHALL REPLACE CASTING AND/OR LID TO PROVIDE FLUSH FIT (1/16" +/-). REPLACEMENT SHALL FIT SPECIFICATIONS AND PERFORMANCE OF EXISTING STRUCTURE. IF SUITABLE REPLACEMENT DOES NOT EXIST, BOTH CASTING AND LID MUST BE REPLACED.



APPROVED

CITY ENGINEER DATE

NOT TO SCALE

MANHOLE ADJUSTED
TO GRADE

CITY OF
HILLIARD, OHIO

STANDARD
CONSTRUCTION DRAWING

1/1

MHA-1